

COMMERCIAL OFFER			
To:		Date:	02/02/2025
Attn:	م. عمر	Project Ref:	
Email:		Quote No:	WOD-TY-SC-25022
Tel No:		Your Ref:	E-MAIL
Mob No:		Project Name:	

**Dear Sir,**

Further to your inquiry, it is our pleasure to submit our quotation of low voltage Panels as per submitted load schedule specification .

## Warranty

Warranty Period Shall be 12 Months from the date of testing & commissioning or 18 Months from the date of delivery whichever comes first.

NO	Name of Panel	Qty of Panel	Unit / Price	Total / Price
1	MCC-01	1	9,978.93	9,978.93
2	MCC-02	1	13,253.56	13,253.56
TOTAL PRICE FOR THE PROJECT		2		23,232.49

TOTAL PRICE / SR	23,232.49
VAT 15% SR	3,484.87
TOTAL PRICE WITH TAX / SR	26,717.37

**TERMS & CONDITIONS:**

QUOTATION: please refer to the above prices. Our offer dose not include any site work.

Payment: 50% Advance 50% Before delivery from factory land.

**Offer Validity:** Our offer remains valid for order acceptance for one week only.

Delivery: 7 - 10 Working days from official P.O & advance payment.

<p><b>Eng. Tareq AL-yousef</b>          Estimation &amp; Technical.dep  <a href="mailto:tareq@wodfa.com">tareq@wodfa.com</a>          Mob: 0533217146</p>	<p><b>Eng. Feras al-jumaa</b>          Production Manager  <a href="mailto:feras@wodfa.com">feras@wodfa.com</a>          Mob: 0500600480</p>
---	--

We trust that our offer meets your requirements. However, if you have any inquiry regarding this quotation, please do not hesitate to contact us at your most convenient time.

**Bank Details : alinma bank / SA3805000068204371635000**

TECHNICAL OFFER			
ITEM No : 01	PANEL NAME : MCC-01	QTY.	1
SYSTEM VOLTAGE	400/230 VAC -60HZ	ENCLOSURE FRAME	1.5 mm
NO. OF PHASE/WIRES	3/4	ENCLOSURE PROTECTION	IP - 55
CONTROL VOLTAGE	230 VAC	ENCLOSURE FINISH	RAL - 7035
Rated Current of Main B.B	MAIN C . B	INCOMING CABLE ENTRY	BOTTOM
Neutral B.B SIZE	100% OF Main C.B	OUTGOING CABLE	BOTTOM
Ground B.B SIZE	50% OF N .B.B	FORMS OF SEPARATION	Form 1
CURRENT DENSITY	1.5A / MM2	B.B PLATING	TIN PLATED

ITEM	DESCRIPTION	QTY	REFERENCE	MAF.
MAIN C.B	NSX100F 36kA AC 3P3D 63A TMD 50 °C	1	C10F3TM063C	Schneider
BRANCHES	GV2ME MOTOR CB THERM/MAG 2.5-4A ROCKER	10	GV2ME08	Schneider
	TeSys GV2 & GV3 - aux contact - 1 NO + 1	10	GVAD1010	Schneider
	3P CONT 9A AC3 4KW 1NO 1NC 220VAC COIL	30	LC1D09M7	Schneider
	MECHANICAL INTERLOCK	10	LAD9V2	Schneider
	Simple Socket mixed terminations 4CO ris	20	RXZE2M114M	Schneider
	Miniature relay 4 CO 230 V AC	20	RXM4AB1P7	Schneider
	SS,3 POSITION,2NO(SHORT)	10	XA2ED33	Schneider
	PB,FLUSH,GREEN,1NO	10	XA2EA31	Schneider
	PB,FLUSH,RED1NC	10	XA2EA42	Schneider
	Pilot Light	10	XA2EVM3LC	Schneider
	Pilot Light	11	XA2EVM4LC	Schneider
	Pilot Light	11	XA2EVM5LC	Schneider
	Medium XA2 Pilot Light,220v AC, Blue	1	XA2EVM6LC	Schneider
	STI 1P 10,3X38 500V	13	A9N15636	Schneider
ENCLOSURE	H1200 x W1000 x D250MM	1	AN.WM.1210.25MP	ANPA/EQ
BUSBAR	Copper Bus BAR 1.5Afor 1MM With N&E	LOT	****	*****
ACC	MP + ACC	1	****	*****

ITEM No : 02		PANEL NAME : MCC-02		QTY.	1
SYSTEM VOLTAGE	400/230 VAC -60HZ	ENCLOSURE FRAME	1.5 mm		
NO. OF PHASE/WIRES	3/4	ENCLOSURE PROTECTION	IP - 55		
CONTROL VOLTAGE	230 VAC	ENCLOSURE FINISH	RAL - 7035		
Rated Current of Main B.B	MAIN C . B	INCOMING CABLE ENTRY	BOTTOM		
Neutral B.B SIZE	100% OF Main C.B	OUTGOING CABLE	BOTTOM		
Ground B.B SIZE	50% OF N .B.B	FORMS OF SEPARATION	Form 1		
CURRENT DENSITY	1.5A / MM2	B.B PLATING	TIN PLATED		

ITEM	DESCRIPTION	QTY	REFERENCE	MAF.
MAIN C.B	NSX100F 36kA AC 3P3D 63A TMD 50 °C	1	C10F3TM063C	Schneider
BRANCHES	ATV212 -30 kW-400V 3phas	1	ATV212HD30N4	Schneider
	Simple Socket mixed terminations 4CO ris	3	RXZE2M114M	Schneider
	Miniature relay 4 CO 230 V AC	3	RXM4AB1P7	Schneider
	SS,3 POSITION,2NO(SHORT)	1	XA2ED33	Schneider
	PB,FLUSH,GREEN,1NO	1	XA2EA31	Schneider
	PB,FLUSH,RED1NC	1	XA2EA42	Schneider
	Pilot Light	1	XA2EVM3LC	Schneider
	Pilot Light	2	XA2EVM4LC	Schneider
	Pilot Light	2	XA2EVM5LC	Schneider
	Medium XA2 Pilot Light,220v AC, Blue	1	XA2EVM6LC	Schneider
	STI 1P 10,3X38 500V	4	A9N15636	Schneider
ENCLOSURE	H1200 x W800 x D250MM	1	AN.WM.1208.25MP	ANPA/EQ
ACC	MP + ACC	1	****	*****

#### TECHNICAL NOTES:

- 1- All are Form-1 construction only.
- 2- The above price only Includes Factory testing and commissioning (it dose not Include Termination and Installation).
- 3- Price and Delivery valid in Riyadh City, Saudi Arabia.